

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.

Farm- Sutor "A"


No. 7

SEC. 13 T. 10 R. 20W
 (approx) SW NW NW

Total Depth. 3721
 Comm. 12-15-56 Comp. 12-24-56
 Shot or Treated.
 Contractor. Garvey Drilg Co.
 Issued. 3-16-57

County Rooks

KANSAS

**CASING:**

8 5/8" 304' cem w/200 sx.
 5 1/2" 3717' cem w/525 sx.

Elevation. 2176 GL

Production. 121 BOPD

Figures Indicate Bottom of Formations.

sand	45
sand, shale	275
shale blue	304
shale blue, shells	900
sand, shale	1250
shale, shells	1450
shale, sand	1610
anhydrite	1645
shale, shells	1735
shale, lime	3225
lime	3304
lime, shale	3346
lime	3665
conglomerate	3712
lime	3715
Arbuckle	3721
Total Depth	

Tops:

Anhydrite	1610 - 1645
Heebner	3388
Toronto	3408
Lansing	3424
Base K.C.	(Scout) 3638
Congl.	(") 3655
Simpson	(") 3694
Arbuckle	(") 3715

Producing formation: Arbuckle