


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY

508 East Murdock, Wichita, Kansas

Company - SCHIO ETAL
Farm - Sutor

No. 1

SEC. 13 T. 10 R. 20W
SE SE SETotal Depth. 3761
Comm. 5-20-49 Comp. 5-30-49
Shot or Treated.
Contractor.
Issued. 10-1-49County. Rocks
KANSAS

Elevation. 2213 2nd

Production. Pot. 190 BOPD, no water

CASING:

8 5/8" 268' cem w/200 sx.
5 1/2" 3757' cem w/150 sx.

Figures Indicate Bottom of Formations.

sand	70
shale, sand	268
cement and plug	268
sand, shale, shells	1575
anhydrite	1615
shale, shells	2220
lime, shale	3450
lime	3687
lime cherty	3720
lime, shale RTD	3759
lime	3761
Total depth	

Tops:

Anhydrite	1575
Topeka	3202
Heebner	3408
Lansing	3446
Conglomerate	3689
Simpson	3740
Arbuckle	3755

SHOWS:

DST 3480-3500, flow oil/20 min.
DP & CO. T.D. 3759
FU 1600' oil 2 hrs. DD
3761 T. D.
P.O. Private test 1284 BOPD
Pot. 190 BOPD, no water.