

WELL LOC BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 E. Hurdock, Wichita, Kansas

Company - SOHIO & RINE DRUG.
Farm - Sutor No. 5

SEC. 13 T. 10 R. 20
NE NE SE

Total Depth. 3764

Comm. 10-7-49

Comp. 10-20-49


Shot or Treated.

Contractor.

Issued. 1-14-50

County. Rooks

KANSAS



Elevation. 2220 Ind.

Production. Deptho 3133 BOPD & trace wtr.

CASING:

8 5/8" cem. w/800 sx. 1627'
5 1/2" cem. w/150 sx. 3764'

Figures Indicate Bottom of Formations.

surface dirt	40
sand, shale	200
shale, shells	775
sand, shale, shells	980
pyrite, sand	1150
sand	1425
shale, shells, red bed	1617
anhyd.	1627
cem	1627
anhyd.	1664
red bed, shale, shells	2115
brkn lime & shale	2310
lime	2600
shale, shells	2645
lime	2690
shale, lime, shells	2770
lime	2935
lime, shale	3395
lime	3730
Congl. sand, lime	3764
Total Depth	

Tops:	
anhyd.	1617
Topoka	3210
Webbner	3418
Dodge	3435
Leasing	3455
Base K. C.	3662
Cong.	3699
Simp.	3740
Arbuckle	3761

8" 1624 5" 3762

DST 3478-3502. 30" 2000' oil BHP 1120"
Fl. Pr. 700# DP & CO to TD 3764.
PU 800' Oil 1/2 hr. 1830 oil 1 1/2 hr.
P.O.P.

Deptho 3133 BOPD & trace wtr.