


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - SOHIO & RINE DRILLING CO., ETAL
Farm - Sutor No. 6

SEC. 13 T. 10 R. 20W
SE NW SE

Total Depth. 3759½
Comm. 12-19-49 Comp. 1-4-50 ✓
Shot or Treated.
Contractor.
Issued. 3-18-50

County. Rocks
KANSAS



Elevation. 2207 Ind

CASING:

8 5/8" 1624' cem w/800 sx.
5 1/2" 3755' cem w/150 sx.

Production. Pot. 122 bbls.

Figures Indicate Bottom of Formations.

surface, dirt, sand	40
sand, shells	365
sand, shale, shells	960
shale, shells	1060
Dakota sand	1330
shale, shells	1619
anhyd.	1624
cement 1624	
anhyd.	1665
shale, shells	2110
lime	2305
lime, shale	2385
lime brkn	2485
lime, shale	2590
lime	2675
shale, shells	2795
shale, lime	3205
lime	3350
lime, shale	3410
lime	3720
shale	3756
lime	3759½
Total depth	

Tops:

Anhydrite	1617
Topeka	3205
Heebner	3414
Dodge	3433
Base Oread	3443
Lansing	3449
Conglomerate	3686
Simpson	3740
Arbuckle	3752

Shows of Oil, Gas, Wtr.

DST 3455-70, 45" 90' O & G C muddy wtr.

BHP 1050.

DST 3475-90 35" 35' muddy wtr & rainbow show Oil

BHP 950'.

DST 3521-66 50" 510' W & S G.

BHP 1100#.

DST 3572-94 45" 15' O & G C M & some free oil

BHP 0#.

DST 3603-26 30" 690' oil 35.3 grav.

BHP 650#.

DP & CO to TD 3756 (1' corr) DD 3757 test 1½

BOPH, 500 A. S. 2½ BOPH 5 hrs.

DD 3759½ T.D. 750 A. S 13 BOPH 4 hrs. P.OP.