


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- NADEL & GUSSMAN
Farm- Stithem No. 23

SEC. 14 T. 10 R. 20W
NE SE NE

Total Depth. 3735'
Comm. 12-28-56 Comp. 1-7-57
Shot or Treated.
Contractor.
Issued. 3-30-57

County Rocks
KANSAS



CASING:

8 5/8" 205' w/135 sx cem.
5 1/2" 3733' w/150 sx cem.

Elevation. 2198' RB

Production. 2773 BOPD

Figures Indicate Bottom of Formations.

surface	205
shale	870
sand-shale	1330
shale-shells	1620
Anhydrite	1665
shale	1940
lime-shale	3140
lime	3640
lime-conglomerate	3720
Conglomerate-Arbuckle	3735
Total Depth RTD	

TOPS:
Heebner 3406
Toronto 3427
Lansing 3444
B/Kansas City 3656
Conglomerate 3680
Simpson shale 3722
Arbuckle 3732
DST #1 - 3590-3620' - open
30 min. - weak blow 9 min.
Rec. 47' mud. BHP 0#, 30 min.

DST #2 - 3614-40' - open 30
min. - weak blow 3 min. Flush-
ed tool twice, rec. 220' slight-
ly oil specked mud. BHP 540#/30".