

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00652

Company - HEATHMAN DRILLING CO., INC.
Farm - Williams No. 1

SEC. 16 T. 10 R. 20W
NW NW NW

Total Depth. 3821
Comm. 3-25-50 Comp. 4-4-50
Shot or Treated.
Contractor. HEATHMAN DRILLING CO., INC.
Issued. 5-6-50

County. Rooks
KANSAS



Elevation. 2244 (m)
2246 RB (2nd)

Production. 352 bbls.

CASING:

8 5/8" 129' com w/100 sx.
5 1/2" 3815' com w/100 sx.

Figures Indicate Bottom of Formations.

sand, shale	130
shale, shells	320
shale	920
sand, shale	1028
shale	1205
sand	1445
shale, shells	1650
shale, red bed	1732
anhydrite	1765
shale, shells	1870
shale	2114
shale, shells	2295
shale, lime	3255
shale	3260
limo	3406
lime, shale	3564
lime	3786
conglomerate	3803
sandy shale	3813
lime RTD	3815
limo	3821
Total depth	

Tops:

Anhydrite	1732
Topeka	3280
Heebner	3485
Lansing-K. 6.	3528
Base Kansas city	3750
Conglomerate	3786
Simpson	3798
Arbuckle	3813

Drilling-in information:

4-7-50 P.M. - Drilled plug. Rainbow
show oil.
DD to 3817 1/2 - no increase.
4-8-50 DD to 3819 - 1/2 boph.
DD to 3821 - 400' oil - hr.
1000' oil-end of 2nd hr
Swabbed 6 boph - 400' OB - 12 hrs.
400 gal. - sub. 15 boph -
1400' oil-end of 2nd hr.