

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY BIRMINGHAM BARTLETT DRILLING CO.


SEC. 25 T. 10 R. 20W

FARM Sutor "C" NO. 1

LOC. SW SW NE

TOTAL DEPTH 3738
 COMM. 11-10-50 COMP. 11-21-50
 SHOT OR TREATED
 CONTRACTOR Birmingham Bartlett
 ISSUED 12-16-50

COUNTY Rocks



CASING

8 5/8" 173' cem w/125 sx.
 5 1/2" OD 3733' cem w/150 sx.

ELEVATION 2151 (m)
 2154 RB and.

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

sand	20
post rock	50
shale, shells	1050
sand	1260
shale, shells	1585
anhyd.	1620
shale, shells	2110
lime brkn	2485
shale, shells	2810
lime, shale	2895
shale, shells	3030
lime, shale	3150
shale, shells	3235
lime, shale	3350
lime	3390
lime, shale	3423
lime	3707
shale, sand	3732
lime RTD	3734
lime	3738
Total depth	

Tops: Scout	
Topeka	3174
Heebner	3385
Toronto	3406
Lansing	3425
Chy. Cong.	3666
Simpson	3721
A _r buckle	3731

Drilling-in information:

11-27-50, deepened 4' to 3738', last
 1 1/2' had show oil; bailed 1 pint oil
 pr hr. Acid w/300 gals. Swbd 12 hrs,
 2138' off bottom.

Recovered 48 bbls water and 5 bbls oil;
 last 8 hrs, all water.

11-28-50, Ran spinner survey, which
 showed that water was coming from
 the formation.

11-29-50. Plugged and abandoned.