

15-163-03405

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company - DERBY OIL CO.  
Farm - Williams No. 1

SEC. 27 T. 10 R. 20W  
NW NW NW

Total Depth. 3781  
Comm. 6-14-51 Comp. 6-25-51  
Shot or Treated.  
Contractor. Champlin Refining Co.  
Issued. 7-28-51

County. Rooks

KANSAS



CASING:

8 5/8" ~~267~~ cem w/175 sxs.

Elevation. 2189.3 DF

216 (RB (and))

Production. dry

Figures Indicate Bottom of Formations.

All measurements are from Kelly Bushing

sand, shale	257
shale, sand, shells	1535
sand, shale, anhydrite	1660
anhydrite, shale	1920
shale, shells	2730
shale	2875
shale, lime	3447
lime	3666
shale, lime	3702
chert, shale	3781 RTD
Total depth	

Tops:

Heebner	3411
Lansing	3447
Base Kansas City	3666
Conglomerate	3702

No shows 3447

Filled hole with mud. Set wood plug at 240', followed by 15 sxs. cem. Filled with mud to 40'. Set wood plug at 40', followed by 10 sxs. cem. to surface.