

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STERLING DRILLING CO. ET AL
Farm- Tribble No. 3

SEC. 28 T. 10 R. 20W
SE NW SW

Total Depth. 3763'

Comm. 3-5-55

Comp. 3-19-55


Shot or Treated.

Contractor. Group Exploration Co., & Sterling Drlg. Co.

issued. 5-28-55

County Rocks

KANSAS



Elevation. 2177 RB.

Production. 130 BO

CASING:

8 5/8" 200' w/125 sx cem.
5 1/2" 3756' w/100 sx cem.

Figures indicate Bottom of Formations

clay-sand	60
shale-shells	650
shale-sand	1370
red bed	1620
shale	1650
Anhydrite	1705
shale-shells	2120
shale-limestone	2475
limestone	2575
shale-limestone	2875
limestone	2960
brkn limestone-shale	3140
sdv shale	3215
limestone	3255
limestone-shale	3340
limestone	3635
shaley conglomerate	3753
Arbuckle limestone	3763
Total Depth	

TOPS: Scout

Anhydrite	1655
Lansing	3460
B/Kansas City	3698
Conglomerate	3711
Simpson	3731
Arbuckle	3755

CABLE TOOLS M.I.C.T.

Swabbed mud & drilled cement.
Swab testee at the rate of 10
bbls. of oil per hr. Acidized
w/500 gal., maximum pressure
750#. Swab tested @ rate of
29 bbls. oil per hr., no wtr.
M.O.C.T.