

15-163-03436


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STERLING DRILLING CO., et al
Farm-Tribble No. 4

SEC. 28 T. 10 R. 20W
NE NW SW

Total Depth. 3741
Comm. 5-25-55 Comp. 6-12-55
Shot or Treated.
Contractor. Sterling Drilling Co.
Issued. 8-20-55

County Rooks
KANSAS



Elevation. 2174

Production. 3000 BOPD

CASING:

8 5/8 200' w/ 125 sx cmt.
5 1/2 @ 3734' w/ 100 sx cmt.

Figures indicate Bottom of Formations.

clay & shale	200
shale	900
sand & shale	1650
anhydrite	1695
red bed & shale	1875
shale & lime	2240
lime	2585
shale & lime	2890
lime	3085
shale & lime	3225
lime	3675
lime & shale	3735
Arbuckle lime	3741
Total Depth	

SCOUT TOPS:

Heebner	3410
Toronto	3430
Lansing	3450
Conglomerate	3700
Arbuckle	3732

MICT. swbd. HD & drld. cmt. HF w/
130' fluid/30 min. Drld new hole 3737
to 3741. 2500' FIH/3 hrs. tstd. @
rate 55 BPH/3 hrs. Acid. w/ 500 gals.
MP 850#, TP 500#. tstd. @ rate 70
BFPH/1 1/2 hrs.