

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-00895

Company- STERLING DRILLING CO., ET AL
Farm- Tribble No. 1

SEC. 28 T. 10 R. 20W
NE SW SW

Total Depth. 3759'

Comm. 12-21-54

Comp. 1-12-55


Shot or Treated.

Contractor. Sterling Drlg. Co. & Red Crow Drlg. Co.

Issued. 3-5-55

County Rooks

KANSAS



Elevation. 2164' RB

Production. 55 BO

CASING:

8 5/8" 200' cem w/125 sx
5 1/2" 3760' cem w/100 sx

Figures indicate Bottom of Formations.

shale	310
sand & shale	1290
shale & limestone	2525
limestone	2605
shale & limestone	2875
limestone	3065
shale	3295
shale & limestone	3370
limestone	3670
limestone & shale	3725
shale & Conglomerate	3750
limestone	3759
Total Depth	

Cable Tools: N.I.C.T. Swabbed mud, drilled shoe and cleaned out to T.D. 3759'. Bail tested for 3 hourst at the rate of one bbl. oil per hour. Ran tubing with packer and acidized with 500 gal. acid. Swabbed back load oil and tested at rate of 2-1/2 bbls. oil per hour. Pulled tubing, re-ran tubing with pumpsat. P.O.P.

Tops: Scout	
Hoebner	3415
Lansing	3454
Conglomerate	3705
Arbuckle	3748