

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-00617

Company- VIRGINIA DRLG. CO.
Farm- Thomas No. 1

SEC. 29 T. 10 R. 20W
NW SW NW

Total Depth. 3701'

Comm. 10-4-52


Comp. 10-17-52

Shot or Treated.

Contractor. Virginia Drlg. Co.

Issued. 7-28-56

County Rocks
KANSAS



Elevation. 2112' DF

Production. 6 BO & NW

CASING:

8 5/8" 225'
5 1/2" 3680'

Figures indicate Bottom of Formations

sand	20
rock	45
shale-sand	130
shale	185
pyrite	188
shale-shells	225
blue shale	650
grey shale	760
sand-shale	1590
anhydrite	1600
lime	1630
shale-shells	2185
lime-shale	2290
broken lime	2400
lime-shale	2500
lime	2655
shale-shells	3097
lime-shale	3304
lime	3353
lime-shale	3449
lime	3687 RTD
lime	3701
Total Depth	

Tops:

Topeka	3156
Heebner	3364
Toronto	3384
Lansing-Kansas City	3405
Base Kansas City	3626
Arbuckle	3679

Ran Lane Wells

Perf. w/20 shots 3587 $\frac{1}{2}$ -3691 $\frac{1}{2}$, water, no oil.