


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- BIRMINGHAM-BARTLETT DRLG. CO.
Farm- Raymond "A" No. 3

SEC. 30 T. 10 R. 20W
C S/2 NE NW

Total Depth. 3690'
Comm. 9-16-58 Comp. 9-25-58
Shot or Treated.
Contractor.
Issued. 1-31-59

County Rooks
KANSAS



CASING:

8 5/8" 205' cem w/150 sx.
5 1/2" 3684' cem w/100 sx.

Elevation. 2102' DF

Production. 140 BOPD

Figures Indicate Bottom of Formations.

clay & sand	70
shale	685
shale & sand	1220
sand	1400
red bed	1566
Anhydrite	1620
shale & shells	2185
shale & lime	3390
lime	3689 RTD
lime	3690 CTTD
Total Depth	

TOPS:

Anhydrite	1566
Heebner	3344
Toronto	3370
Lansing-Kansas City	3383
Conglomerate	3649
Simpson	3665
Arbuckle	3680

DST #1 3534-60, op 15 min, weak blow
for 2 min. Rec. 7' mud. BHP 0#.

DST #2 3680-84, op 30 min., rec. 6' mud
BHP 160#.

DST #3 3681-89, op 1 hr., rec. 140' oil
cut mud. BHP 100#.