

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company—CITIES SERVICE OIL CO.
Farm—Schneider No. 1

SEC. 31 T. 10 R. 20W
NW NW SW
330' S & 330' E of W/4C

Total Depth. 3680

Comm. 8-7-55

Comp. 8-24-55


Shot or Treated.

Contractor. Lohmann-Johnson Drilling Co., Inc.

Issued. 11-19-55

County Rooks

KANSAS



Elevation. 2116

Production Pot. 242 BOPD, NW

CASING:

8 5/8 @ 240' w/ 175 sx cmt.
5 1/2 @ 3675' w/ 175 sx cmt.

Figures indicate Bottom of Formations.

shale	240
shale, sand & shells	1315
sand & shale	1555
anhydrite	1595
shale	1670
shale & shells	2245
shale & lime	2505
lime	2560
lime & shale	3675
lime	3677
SLM	3676
lime	3680

Total Depth

3677 Rotary TD = 3676 SLM

TOPS: (corrected)

Topeka	3135
Heebner	3335
Dodge	3357
Lansing	3369
Conglomerate	3640
Erosional Arbuckle	3671
Arbuckle	3674
Penetration	6

FILLUP:

579' oil in 1 hr. 10 min.
919' oil in 1 hr. 40 min.
1189' oil in 2 hrs. 10 min.
1792' oil in 3 hrs. 15 min.
2105' oil in 3 hrs. 45 min.
2300' oil in 4 hrs. 15 min.
2910' oil in 9 hrs. 5 min.