

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. CITIES SERVICE OIL CO.  
Farm. Schneider No. 2

SEC. 31 T. 10 R. 20W  
SE NW SW  
1650' N & 990' W of SWc

Total Depth. 3663  
Comm. 9-18-55 Comp. 10-9-55  
Shot or Treated. 500 Gal. acid  
Contractor. Lohmann-Johnson Drilling Co., Inc.  
Issued. 12-24-55

County Rooks  
KANSAS



CASING:  
8 5/8 @ 240' w/ 175 sx cmt.  
5 1/2 @ 3656' w/ 175 sx cmt.  
Howco stage collar @ 1549' w/ 600 sx cmt.

Elevation. 2091

Production. 224 BOPD, NW

Figures indicate Bottom of Formations.

sand & shale	240
shale & shells	550
shale, shells & sand	1115
shale & shells	1448
shale & sand	1525
anhydrite	1565
shale	2070
shale & lime	2430
lime	2490
lime & shale	3663
SIM correction	3656
lime	3663
Total Depth	

TOPS: (corrected)	
Topeka	3114
Heebner	3318
Dodge	3340
Lansing	3359
Cherty conglomerate	3623
Erosional Simpson	3643
Arbuckle	3655
Penetration	8

FU:  
80' oil/20 min. @ 3660  
134' oil/ 50 min @ 3660  
179' oil/1 hr. 20 min. @ 3660  
890' oil/15 hrs. 40 min. @ 3660

Acidized, pumped 195 BO, NW/24 hrs.

Deepened 3660-3663