


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. CITIES SERVICE OIL CO.
Farm- Schneider No. 3

SEC. 31 T. 10 R. 20W
NW SW SW
990' N & 330' E of SWc

Total Depth. 3695
Comm. 10-6-55 Comp. 10-24-55
Shot or Treated. 500 gal. acid
Contractor. Lohmann-Johnson Drilling Co., Inc.
Issued. 12-24-55

County Rocks
KANSAS



8 5/8 @ 240' CASING w/ 175 sx cmt.
5 1/2 @ 3691' w/ 175 sx cmt.
Baker cementing collar @ 1585' w/ 600 sx cmt. Elevation. 2118
Production. 300 BOPD, NW

Figures indicate Bottom of Formations.

shale	41
sand & shale	240
shale & shells	755
sand, shale & shells	1345
shale & sand	1555
anhydrite	1595
shale	2000
shale & lime	2140
lime	2225
shale & lime	2420
lime	2585
lime & shale	3005
shale	3125
lime & shale	3616
conglomerate	3680
lime	3698
SLM correction	3692
lime	3695
Total Depth	

TOPS: (corrected)	
Topeka	3151
Heebner	3347
Dodge	3370
Lansing	3387
Cherty conglomerate	3640
Erosional Simpson	3665
Arbuckle	3690
Penetration	5

FU:
553' oil/2 hrs.
985' oil/3 hrs.
1328' oil/4 hrs.
1605' oil/5 hrs.
2715' oil/15 hrs.