


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm- Schneider No. 2

SEC. 31 T. 10 R.20W
SW SW NW

Total Depth. 3785'
Comm. 10-12-55 Comp. 11-5-55
Shot or Treated.
Contractor. Badgers Drlrs. Inc.
Issued. 2-18-56

County Rooks KANSAS



CASING:
9 5/8" 280' cem w/225 sx
5 1/2" 3784' cem w/175 sx

Elevation. 2135' DE

Production. State Pot. P 251 B0,
NW in 24 hrs.

Figures indicate Bottom of Formations.

surface soil	281
shale & shells	470
shale	920
red bed & shale	1090
sand	1280
shale	1375
shale & shells	1565
anhydrite-iron sand	1600 ✓
red bed	1625
red bed, shale & shells	1970
lime & shale	2480
lime	2540
shale	2770
lime & shale	3208
lime	3708
Arbuckle Dolomite	3785
Total Depth	

Tops:
Topeka 3157
Heebner 3362
Toronto 3385
Lansing-Kansas City 3401
Cherty Conglomerate 3672
Arbuckle 3699

DRILL STEM TESTS:

- # 1 3177-3215, open 1 hr., fr blow increasing to gd, rec. 170' MSW w/SSO on top, FP 30-80# BHP 1080#/20 min.
- # 2 3580-3605, open 1 hr., fr blow increase to good rec. 245' fluid (20' oil, 165' HO & GCM) 60' O & GCM, FP 30 - 80#, BHP 1160#/20 min.
- # 3 3698-3708, open 1 hr., wk blow increase to str., rec. 230' fluid, BHP 870#/20 min.