


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM COMPANY
Farm- Aaron Thomas No. 2

SEC. 31 T. 10 R. 20W
SW SW SE

Total Depth. 3657'
Comm. 2-6-57 Comp. 3-2-57
Shot or Treated.
Contractor. Brack Drilling Company
Issued. 5-4-57

County Rocks
KANSAS



Elevation. 2054'

Production. 170.7 BOPD
Allowable 25 BOPD

Figures indicate Bottom of Formations. (State Potential)

sand & shale	125
shale & shells	320
shale, shells & sand	710
shale & lime	990
sand	1265
sand & shale	1420
Anhydrite	1480
shell & sand	1526
lime & shale	1546
shale & shells	1810
lime & shale	3361
lime	3552
lime & shale	3615
lime & chert	3657 RTD
Total Depth	

TOPS	
Topeka	3092
Heebner	3301
Toronto	3323
Lansing/Kansas City	3339
Base/Kansas City	3558
Pennsylvania	
Conglomerate	3590
Simpson Sand	3625
Arbuckle	3637

DRILL STEM TESTS

DST #1 3513-3550' Op. 1 hr.
good blow thr-out test, gas
to surface in 40 min. too
small to measure. Rec. 550'
fluid, 190' clean gassy oil,
360' HO & GCM, IF 30#,
FF 180#, BHP 1060#, SI 20 min.

DST #2, 3640-3655, op. 1 hr.
weak blow thr-out test rec.
105' fluid, 75' HO CM, 30' GCM,
IF 25#, FF 50#, BHP 1020#,
SI 20 min.