


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DERBY OIL COMPANY
Farm- Schneider No. 1

SEC. 32 T. 10 R. 20W
NE NE NW
2310' fr WL, 330' fr NL

Total Depth. 3770'
Comm. 3-25-54 Camp. 4-5-54
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 5-1-54

County Rocks
KANSAS



CASING:
8 5/8" 221' cen w/150 sx

Elevation. 2156' DF

Production. Dry

Figures indicate Bottom of Formations.

sand, shale & shells	221
shale	680
sand & shale	760
shale	1100
shale & sand	1620
anhydrite	1665
shale & shells	2155
shale & lime	2465
lime	2620
shale & lime	3225
lime	3365
lime & shale	3440
lime	3680
conglomerate	3730
shale & lime	3750
lime	3770 RTD
Total Depth	

Tops:	
Heebner	3399
Lansing	3437
Base Kansas City	3660
Conglomerate	3696
Simpson Shale	3738
Reworked Arbuckle	3744
Arbuckle	3750

DRILL STEM TESTS:

#1 Topeka, 3203-3230, open 1 hr, Weak
stdy blow 60 min, rec. 54' sl salty muddy
wtr. BHP 900#

#2 Lansing, 3475-3482, open 45 min., Weak
blow 4 min., rec. 29" sl muddy salt wtr.
BHP 1360#

#3 Lansing 3622-3638, open 1 hr, Rec 60'
VSIO & GCM. BHP 170#

#4 Reworked Arbuckle, 3746-3752, open 30 min.
Weak blow 5", rec. 3' rotary mud. BHP 0#

#5 Arbuckle, 3752- 3757, open 30 min. Rec.
5' rotary mud. BHP 0#

#6 Arbuckle 3752-3770, open 1 hr., Weak
blow 6", rec. 10' mud. BHP 0#