


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - FRANCIS OIL & GAS - VEEDER SUPPLY COMPANY SEC. 32 T. 10 R. 20W
Farm - Schneider No. 1 SE SE SW

Total Depth. 3750
Comm. 4-27-50 Comp. 5-10-50
Shot or Treated.
Contractor. Veeder Supply & Development Company
Issued. 6-3-50

County. Rooks

KANSAS



Elevation. 2106 feet

Production. Dry

CASING:

8 5/8" csg set at 270', w/150 sx cement

Figures Indicate Bottom of Formations.

surface soil gravel	140
shale	270
shale	400
shale & shells	1050
sand (Dakota)	1310
shale	1465
shale & shells	1475
rodbod	1565
anhydrite	1625
shale & shells	2120
lime, shells & shale	2175
lime & shale	2255
shells & shale	2310
lime & shale	2405
lime, shells & shale	2470
lime & shale	2615
lime	2705
lime & shale	2935
lime, shale & shells	3035
lime & shale	3095
shale	3135
lime	3325
lime, shale breaks	3340
lime	3590
lime & shale	3670
conglomerate (Cherty)	3705
simpson	3708
arbuckle lime chert	3750
Total depth	

Scout Tops:

Topeka	3154
Heebner	3365
Dodge	3387
Lansing	3402
Conglomerate	3668
Simpson	3705
Arbuckle	3708

Remarks:

Drill stem test 3310-21, open 1 hour,
rec. 25' OCM & 30' water