

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas

Company. COLORADO OIL & GAS CORPORATION  
Farm. Schneider No. 2

SEC. 32 T. 10 R. 20W  
C E/2 SE NW  
660' fr SL, 2310' fr WL

Total Depth. 3775

Comm. 6-8-55

Comp. 7-4-55


Shot or Treated.

Contractor. (RT) G-M-R Oil Co. (CT) Leigan Drilling Co.

Issued. 9-17-55

County Rooks

KANSAS



CASING:

8 5/8 @ 235' w/ 125 sx cmt.  
5 1/2 @ 3775' w/ 100 sx cmt.

Elevation. 2155 DF

Production. Pot. 136 BOPD, 15%W

Figures indicate Bottom of Formations

surface clay, shale & sand streaks	90	perf/ 12/3606-09, 2 hr swb. tst. avgd. 1.26 BO, 1% WPH, acid 1000 gal. MP 500#, fin. on 500#, 1" PD 100#, 2" PD 125#, 5" PD 165#, 30" PD 200#, rec. flush. 3 hr. swb. tst. avgd. 1.67 BFPH, 8% wtr. Ran tbg. set packer @ 3590', displaced 50 sx cmt in formation, 2000# standing press. DC to 3617'. Zone 3606-09 making 15 GFPH, 50% wtr. Perf. 12/3606-09 & 16/3596-3600. Acid 2000 gal. MP 575#, fin. on 575#, 1" PD 25#, 5" PD 75#, 15" PD 175#, 45" PD 225#. Did not rec. load. Set plug @ 3579'. Perf. 16/3564-68, Tested 10 1/2 GOPH; trace wtr. Acid 1000 gals. MP 600#, fin. on 600#, 1" PD 50#, 5" PD 100#, 10" PD 150#, 45" PD 350#. Tested 5.01 BOPH, 15% wtr. Drld. bridge plugs & CO to 3658'. 4 hr. test avgd. 6.47 BOPH, 13% wtr.
shale	816	
Dakota sand	846	
shale	1072	
sand & shale streaks	1290	
shale & sand streaks	1350	
red bed	1608	
anhydrite	1650	
shale	2000	
salt	2090	
lime & shale	2304	
shale w/ lime streaks	2510	
shale & lime	2870	
shale w/ lime streaks	2975	
lime & shale	3345	
lime	3632	
lime & chert	3692	
lime	3727	
lime & chert	3742	
lime	3775	
Total Depth		All KB Meas. 5.80' above BH.

TOPS:

Heebner	3391
Toronto	3412
Lansing	3429
Base KC	3652
Conglomerate	3671
Reworked Arbuckle	3734

DST #1: 3510-20, open 1 hr. fair stdy blow 1 hr. rec. 90' SOCM, 60' SW, very sl. scum oil, BHP 1170#/20 min.

DST #2: 3558-3600, open 1 hr. vry. strg. bl. 1 hr. rec. 840' gas, 355' muddy gassy oil, FP 0-90#, BHP 1125#/20 min.

DST #3: 3607-32, open 1 hr. wk. bl. 5 min. rec. 20' mud, BHP 0#

DST #4: 3735-40, open 1 hr. wk. bl. 5 min. rec. 15' mud, BHP 0#

CO to 3661, perf 16/3644-48, show oil on gun, 3 hr BT avgd. 1 GWPH w/ scum oil, acid w/ 500 gal. MP 1200#, broke to 475#, fin. on 475#, 1" PD 100#, 5" PD 150#, 30" PD 250#, rec. flush; Swb. 1st hr 1.26 BO, 2nd hr. .42 BO, 3rd. hr. 1 BO, next 3 hrs. .50 BO, acid w/ 2000 gals. MP 600#, fin. on 600#, 1" PD 25#, 5" PD 150#, 30" PD 250#, rec. flush, 7 hr swb. tst. avgd. 1.68 BO, 2% WPH, set plug @ 3625,