


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.
 Farm- Towns No. 3

SEC. 33 T. 10 R. 20W
 SW NW NE
 1650' N & 330' E of center

Total Depth. 3714
 Comm. 3-5-55 Comp. 3-21-55
 Shot or Treated. Acid 500 gals (3-22-55)
 Contractor. Lohmann-Johnson Drlg Co., Inc.
 Issued. 4-30-55

County _____ Rocks
 KANSAS



Elevation. 2142

Production. Phy. pct. 247 oil &
 no wtr in 24 hrs.

CASING:

8 5/8" 229' cem w/175 sx
 5 1/2" 3710' cem w/175 sx

Baker stage collar @ 1622' Figures indicate Bottom of Formations.
 cem w/500 sx.

sand, shale	230
sand, shale, shells	1420
shale, shells	1602
anhydrite	1641
shale, shells	1645
sand, shale	1950
lime, shale	2900
shale	3025
lime, shale	3708
lime	3710
3710 RTD = 3710 SLM	
lime	3714
Total Depth	

Tops:	
Topeka	3172
Heebner	3377
Dodge	3398
Lansing	3413
Conglomerate	3660
Simpson	3692
Arbuckle	3708
Penetration	6 ft

Fillup: 580' oil in 40 mins.
 760' oil in 1 hr. 10 mins.
 902' oil in 2 hrs. 20 mins.