

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


Company- D.G. HANSEN  
Farm- Veatch No. 1

SEC. 34 T. 10 R. 20W  
NE NE SE

Total Depth. 3750'  
Comm. 2-15-58 Comp. 3-4-58  
Shot or Treated.  
Contractor.  
Issued. 4-12-58

County Rooks

KANSAS



CASING:  
8 5/8" 174.33'

Elevation. 2135' RB

Production. Dry

All Meas. fr RB

Figures indicate Bottom of Formations.

shale	174
shale, sand	610
sand	800
shale, shell	1290
red bed	1565
anhydrite	1605
shale, shell	2110
lime, shale	3313
lime	3340
lime, shale	3419
lime	3462
lime, shale	3494
lime	3750
Total Depth	

TOPS:

Anhydrite	1565
Topeka	3162
Heebner	3373
Toronto	3395
Lansing	3411
E/Kansas City	3625
Conglomerate	3657
Simpson shale	3696
Arbuckle	3714

DST #1-3435-62. Open 2 hr. Wk.  
Steady blow. Rec. 120' MW. IBHP-  
1215 & 735# FBHP

DST #2-3475-94. Open 1 1/2 hr. Rec.  
500' MSW. IBHP-1170#, FBHP- 1025#.

DST #3-3576-1610. Open 1 1/2 hr. Rec.  
12' mud. FBHP-45#.

DST #4-3715-19. Wk. blow 5". Rec.  
15' mud & no pressures.

DST #5-3715-23. Wk. blow 6". Rec.  
16' VSOCM with FBHP-605#.

DST #6-3722-30. Wk. blow 12", Rec.  
16' mud. IBHP-1050# & FBHP-880#.