

15-005-71837

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SKELLY OIL CO.

FARM Vera V. White NO. 5


SEC. 2 T. 10 R. 21W

LOC. SW SE SW

330' fr S.L. 1650' fr W. L. of SW $\frac{1}{4}$   
Sec. 2

COUNTY Graham

KANSAS



TOTAL DEPTH 3799

COMM. 12-1-50

COMP. 12-14-50

SHOT OR TREATED

CONTRACTOR Claude Wentworth Drilling Co.

ISSUED 3-24-51

CASING

8 5/8" 285' cem. w/150 sx

5 1/2" 2581' cem. w/200 sx

ELEVATION 2232 DF

PRODUCTION Pot. 2943 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil, sand & rock	95
shale & shells	290
sand, shale & shells	440
shale & lime	990
shale & shells	1735
anhydrite	1740
shale & shells	2270
lime & shale	2505
lime	2620
lime & shale	3395
lime	3509
lime & shale	3580
lime	3655
lime & shale	3710
lime	3791
grey & brown coarsely xyn dolomite	3799
Total Depth	

Tops:

Topeka Lime	3265
Heebner Shale	3444
Lansing Lime	3484
Conglomerate	3762
Simpson Sand	3773
Arbuckle Lime	3791

12-19-50 500 gals. shot between 3792' & 3799'

12-20-50 1500 gals. shot between 3792' & 3799'

Good porosity & saturation 3791' - 3799'

Producing Formation Arbuckle Lime 3792' - 3799'

Reamed 9-7/8" hole to 12-1/4"