

15-005-71841

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY  
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY SKELLY OIL CO.

SEC. 2 T. 10 R. 21W

FARM Vera V. White NO. 7

LOC. SW NW SW

990' fr N.L. SW/4 330' fr W.L. of Sec.2

COUNTY Graham

TOTAL DEPTH 3903


COMM. 1-17-51

COMP. 2-3-51

SHOT OR TREATED

CONTRACTOR Claude Wentworth Drilling Co.

ISSUED 3-24-51



CASING

8 5/8" 302' cem. w/150 sx

ELEVATION 2286 DF

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil & clay	25
sand	45
clay & shale	120
sand	225
shale & shells	302
shale	860
shale & shells	1585
shale	1780
anhydrite	1800
shale	2060
salt & shale	2135
shale & lime	2605
shale & shells	2720
lime & shale	2805
lime	3080
shale & lime	3220
lime	3589
medium xyln lime	3593
lime	3744
oolitic lime	3750
lime	3795
shale & lime	3843
cherty conglomerate	3847
lime	3873
medium to coarsely	3880
xyln, lgt gry dolomite	3880
lgt, gry finely xyln	3880
dolomite	3903
Total Depth	

Tops:

Heebner Shale	3507
Lansing Lime	3548
Conglomerate	3807
Simpson	3865
Arbuckle Lime	3873

Light stain, poor porosity,  
no odor. 3744-3750

Ran Halliburton drill stem  
test, packer set at 3842',  
open 1 hr. fair blow for 15  
mins., quit blowing at end  
of 30 mins. rec. 62' of  
drilling mud, no oil, BHP-275#  
Poor porosity and stain, no  
odor. 388-2903

Peamed 9-7/8" hole to 12-1/4"

Heavy oil stain, poor por. & sat.