

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-065-01672

Company- ANDERSON-PRICHARD OIL CORP.
 Farm- Miller No. 1

SEC. 3 T. 10 R. 21W
 SW SW SW

Total Depth. 3829

Comm. 9-10-50

Comp. 9-21-50


Shot or Treated.

Contractor. Birmingham-Bartlett

Issued. 9-15-51

County Graham

KANSAS



CASING:

10 3/4" 244' com. w/160 sx.

5 1/2" 3827' com. w/125 sx.

Elevation. 2257 (D.P.)

Phys.

Production. 434 bbls.

Figures Indicate Bottom of Formations.

surface	244
shale	880
sand & shale	1200
sand	1450
shale	1530
shale & red bed	1725
anhyd.	1765
shale & shells	2090
shale	2275
shale & limo	2905
shale & shells	2995
shale	3170
shale & limo	3515
limo	3770
limo & congl.	3815
congl.	3826
Arb.	3828 RTD
Arb.	3829
Total Depth	

Tops:

Hoebner	3460
Lansing	3499
Congl.	3780
Simpson shale	3795
Simpson dolo.	3815
Arb.	3828

D.S.T. 3674-3704 open 45 min. rec.

30' heavily oil cut mud, some free oil

275" BHP

DP & DD 1' TD 3829. Swb. 45 BFPH/2 hrs.

1000' off bottom. The sw b. 19 1/2 BO

45 min., 1450' off bottom. Put on pump.