

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


15-065-01679

Company- ANDERSON-PRICHARD OIL CORPORATION
Farm- Miller No. 10
(Twin to #1)

SEC. 3 T. 10 R. 21W
55' E C - SW SW SW

Total Depth. 3824
Comm. 3-17-52 Comp. 3-28-52
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 5-24-52

County Graham
KANSAS



CASING:
8 5/8" 200' cem.
5 1/2" 3824' cem.

2251 (m)
Elevation. 2251 R.B.
2253 (2d)
Production. 137 bbls / 15% wtr

Figures indicate Bottom of Formations.

surface clay	40
sand, shale	100
shale	1715
anhydrite	1755
shale, shells	2350
lime, shale	2475
lime	2725
lime, shale	3415
lime	3520
lime, shale	3590
lime	3824
Total Depth	

Tops:
Anhydrite 1725
Topeka Not logged
Heebner 3457
Lansing 3497
Conglomerate 3767
Simpson (sst.) 3808
Arbuckle 3821

DST #1 3777-3813, open 45
min., weak 6 min. blow, rec.
10' mud with few spots heavy oil
BHP 0.

Set 5 1/2" @ 3822, cem in two stages-
no returns, WOCT MICT, Drilling
cem. 3780'. Cleaned out to RTD @
3824 swab. 2 BW (no time)- dumped
60 gal. acid to clean up for. -
bailed out on 5 hr. swb. test. made
1 1/2 BO / 7 1/2 BW testing. Az. w/250.
gal. Max. press. 325# no break. swb.
back 80 B load wtr. (total load 95 B)
Swbg. 1200' off bottom. Swb. 2 1/4 NFPH 90%
wtr (probably Dakota wtr) to DD 18 hr.
swb. test 56 BO 11 BW preparing to run
tubing & rods.
4-23: Pumped 120 BO / 15% wtr/20 hrs.,
15-54" SPM.
4-26: State Test 131 BOPD / 15% wtr 15-54" SPM