

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-065-01692

Company- PHILLIPS PETROLEUM COMPANY  
Farm- Tribble No. 7

SEC. 3 T. 10 R. 21W  
CE/2 NW NE

Total Depth. 3846  
Comm. 12-3-51 Comp. 1-4-52  
Shot or Treated.  
Contractor.  
Issued. 2-9-52

County Graham  
KANSAS



CASING:  
8" 338' cem w/300 sx  
5" 3835' cem w/700 sx

Elevation. 2294' DE

Production. I.P. 3000 BOPD

Figures Indicate Bottom of Formations.

sand, shale 497  
sand, shale, pyrite 1137 ✓  
sand, shale, redbed 1772  
anhydrite, redbed, shale 1892  
shale, shells 2027  
lime, shale 2152  
shale, lime strks 2260  
lime, shale 2510  
shale, lime strks 2651  
lime, shale 2878  
shale, chalk, lime 2998  
lime, shale 3508  
lime cherty, shale 3551  
lime, shale 3846  
Total depth

Tops:  
Anhydrite 1762  
Base Anhydrite 1810  
Howard 3278  
Shawnee 3307  
Heebner 3488  
Toronto 3508  
Lansing-Kansas City 3524  
Base Lansing-K.C. 3750  
Arbuckle 3833