

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-D65-02411

Company- NATURAL GAS & OIL & COOP. REFG. ASSOC.
Farm- Smith No. 5SEC. 5 T. 10 R. 21W
SW NW NW

Total Depth. 3910

Comm. 9-14-53

Comp. 9-28-53


County Graham

KANSAS

Shot or Treated.

Contractor.

Issued. 10-24-53



CASING:

10 3/4" 160' cem. w/170 sx

Elevation. 2310 RB

Production. Dry

Figures indicate Bottom of Formations.

clay	5
sand, shale	80
shale	240
shale, shells	280
chalky lime	330
shale, shells	950
shale, sand	1010
shale, shells	1300
sand	1530
shale, shells	1795
anhydrite	1837
shale, shells	2075
lime, shale	3500
shale	3503
lime	3535
lime, shale	3545
lime	3800
lime, shale	3830
shale, lime, chert	3884
shale	3895
arbuckle lime	3910
Total Depth	

Tops:

Anhydrite	1795
Heebner	3500
Toronto	3529
Lansing	3542
Base-Kansas City	3775
Marmaton	3835
Cherty Congl.	3867
Simpson	3881
Arbuckle	3895

DST: #1 3544-90' open 1 hr.
rec. 185' watery mud no BHP.DST: #2 3608-35' open 1 hr.
fair steady blow, rec. 1290'
slightly oil & gas cut salt
water. BHP 1170#.DST: #3 open 1 hr. rec. 25'
oily mud. no BHP.DST: #4 open 1 hr. rec. 70'
slightly muddy wtr. BHP 8000#.DST: #5 open 1 hr. fair steady
blow through out, rec. 330'
sulphur wtr BHP 1250#.