

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-065-01021

Company- EDWIN BRADLEY, DEEP ROCK & BARNETT DRLG.

SEC. 6

T. 10

R. 21W

Farm- Beecher

No. 1

NE NE NW

330' S of NL, 2310'

E of WL of NW/4

County Graham

KANSAS

Total Depth. 3882½


Comm. 7-30-51

Comp. 8-20-51

Shot or Treated.

Contractor. Barnett Drlg.

Issued. 12-8-51



CASING:

8 5/8" 144' cem w/125 sxs.

5½" 3881½' cem w/125 sxs.

Elevation. 2301 DE

Production. pmp. pot. 194.58 bbls.

Figures Indicate Bottom of Formations.

surface, shale	30
sane	50
shale	235
post rock, shale	305
shale	795
shale, shells	910
sand	995
shale, shells	1300
sand	1465
shale, shells	1770
anhydrite	1812
shale, shells	2225
shale	2375
shale, shells	2751
shale, lime	3345
lime	3450
lime, shale	3495
lime	3882½ RTD
Total depth	

Tops:

Heebner	3488
Toronto	3507
Lansing	3525
Base Kansas City	3750
Conglomerate	3860
Simpson	3865
Arbuckle	3880

Drill Stem Tests:

1 3549-3576 tool open 1 hr.
 good blow. Rec. 780' salt wtr.
 slightly gaseous. BHP 650#
 2 3592-3620' tool open 1 hr.
 Strong blow. Rec. 480' gas,
 125' oil cut mud & 120'
 mud cut oil. BHP 1150#.
 flow. Press. Off

Schlumberger T. D. 3881