

AUG 23 1969

7-10S-21W

15-065-20216


CONTRACTOR'S WELL LOG

CONTRACTOR: *Q Co*
WELL NAME:
LOCATION:
GEOLOGIST:
SPUD DATE:
COMPLETION DATE:

Abercrombie Drilling, Inc.
McClellan #1
SE NW NW, Sec. 7-10S-21W
Graham County, Kansas
Orlin R. Phelps
May 2, 1969
May 12, 1969

oil

0	30	Clay
30	75	Sand
75	1300	Shale
1300	1560	Sand
1560	1810	Red Shale
1810	1850	Anhydrite
1850	2000	Shale
2000	2325	Shale & Lime Streaks
2325	2685	Shale & Lime
2685	2822	Lime & Shale
2822	2990	Shale & Lime
2990	3096	Lime
3096	3465	Lime & Shale
3465	3530	Lime w/Shale Streaks
3530	3835	Lime
3835	3877	Lime & Chert
3877	3929	Lime
	3929	Rotary Total Depth



Drilled 245' of 9" surface hole and set 7" csg. @236' w/100 sx. cement. Cement circulated.
Plug was down 2:15 p.m., 5-2-69.
Set 4 1/2" csg. @3926' w/50 sx. 50-50 posmix, 2% gel, 12# gilsonite & 100 sx. 60-40 posmix,
2% gel, 10% salt, 1% c.c. Plug was down 11:15 a.m., 5-12-69.

FORMATION SAMPLE TOPS

ELEVATION

T/Anhy. 1810 (+ 517)
Heebner 3518 (-1191)
Lansing 3557 (-1230)
Arbuckle 3922 (-1595)
R.T.D. 3929 (-1602)

2327 K. B.
2325 D. F.
2319 G. L.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack K. Wharton, Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the McClellan #1, SE NW NW, Sec. 7-10S-21W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

By: *Orlin R. Phelps*