

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-00841


Company. D. G. HANSEN
Farm. McElroy

No. 1

SEC. 7 T. 10 R. 21W
SE SE SE

Total Depth. 3843'
Comm. 4-15-59 Comp. 4-24-59
Shot or Treated.
Contractor. C-G Drlg.
Issued. 9-5-59

County Graham
KANSAS



CASING:

8 5/8" 175'
5 1/2" 3834'

Elevation. 2297' KB

Production. 800 BOPD

Figures indicate Bottom of Formations.

All meas. from top of RB.

sand-shale	175
shale-sand	1730
Anhydrite	1817
shale-red bed	2100
shale-shell	2380
shale-lime	2640
lime-shale	2955
shale-lime	3085
lime-shale	3590
lime	3728
lime-shale	3760
lime	3775
lime-shale	3842 RTD
lime-shale	3843 CTTD
Total Depth	

TOPS:

Anhydrite (scout)	1780
Topeka	3295
Heebner	3503
Toronto	3522
Lansing	3542
Base Kansas City	3771
Marmaton	3783

DST #1 3569-90', op 1 hr., rec. 20'
VSOCM, BHP 680#.

DST #2 3612-25', op 1½ hrs., Rec. 815' fluid,
90' OCM, 180' wtry OCM, 300' Oil & Wtr
60% Oil, 245' wtr. BHP 1100#.

DST #3 3689-3728', op 1/2 hr., rec. 12'
mud, BHP 100#.

DST #4 3723-60', op 2 hrs. rec. 150'
VLTOCM & 50' Oil, BHP 300#.

DST #5 3833-42', op 2 hr., rec. 1235'
Oil BHP 600#.