

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-03028

Company-SKELLY OIL COMPANY

Farm- Roy Martin No. 3

SEC. 9 T. 10 R. 21W

NE SE NW

330' f EL, 990' f SL, NW¼

Total Depth. 3873 PB 3824

Comm. 4-30-56 Comp. 5-12-56


Shot or Treated.

Contractor. Claude Wentworth Drlg Co., Inc.

Issued. 7-7-56

County Graham

KANSAS



Elevation. 2274 D.F.

Production. Pot. 474 bbls oil.

CASING:

8 5/8" 322' cem w/175 sx.

5 1/2" 3870' cem w/175 sx.

Figures indicate Bottom of Formations.

surface soil, rock & shale	94	Tops:	Anhydrite	1765
shale, shells	322		Base Anhydrite	1808
shale	950		Wellington	2124
shale, shells, sand	1475		Base Wellington	2303
shale, red bed	1762		Neva	2786
anhydrite	1810		Near Topeka	3290
shale, shells	2040		Heebner shale	3491
lime, shale	2785		Toronto lime	3518
shale, shells	3035		Lansing lime	3530
lime, shale	3566		Base Kansas City lime	3754
lime tan to gry, fine xylm, spotted poro.	3570		Congl.	3809
lime	3573		Arbuckle lime	3869
lime lgt tan, fine xylm		DST: Ran by Halliburton #1, packer set at 3558, used 65' anchor, op. 1 hr, weak blow inc. to fair blow throughout test. rec. 120' of heavily oil cut mud, IFP 03#, FFP 70#, BHP 210#.		
Poor poro. spotted stn & sat.	3576			
lime	3586			
lime tan & gry, dns xylm, poor poro., spotted sat.	3590	#2, packer set at 3652, used 85' anchor, open 1 hr. weak blow inc. to strong blow, rec. 120' of gas, 150' oil cut mud, IFP 0#, FFP 70#, BHP 280#.		
lime	3592			
lime xylm tan & gry dns, poor poro., spotted sat.	3595	5-19-56 500 gals acid	3688-3712	
lime	3607	5-20-56 2500 "	3688-3712	
limegry vug., poor poro, spotted sat.	3610	5-21-56 500 "	3588-3612	
lime	3612	5-22-56 2500 "	3588-3612	
lime, gry & tan, fine xylm. Fair poro., spotted sat.	3616	Producing Formation-Lansing lime	3588-3712	
lime	3664	Phy. pot. 157.76 BO & no wtr.		
lime dnse tan	3666			
lime	3686			
lime, tan, dense	3696			
lime	3700			
lime lgt tan, fine xylm. Poor poro., spotted sat.	3704			
lime	3707			
lime lgt tan, fine xylm. Poor poro., spotted sat.	3711			
lime	3724			
lime slightly vug. Slight show of free oil in sample	3731			
lime	3737			
lime, shale	3650			
lime	3869			

lime gry to tan, finely xylm dolo. Poor poro. spotted sat. few specks of dead oil.

Total Depth PB 3824