

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-03033

Company- C - G DRLG. CO.
Farm- Hunt-Behrens No. 5

SEC. 12 T. 10 R. 21W
NE SE SE

Total Depth. 3824'
Comm. 1-9-56 Comp. 1-18-56
Shot or Treated.
Contractor.
Issued. 6-9-56

County Rooks KANSAS



Elevation. 2213' BB

Production. 66 BOPD

CASING:

8 5/8" 181.25' cem w/165 sx
5 1/2" 3823.85' cem w/125 sx

Figures indicate Bottom of Formations.

| | |
|-----------------|------|
| surface | 181 |
| shale | 500 |
| shale | 850 |
| sand | 950 |
| shale | 1250 |
| sand | 1495 |
| red bed | 1525 |
| red bed & shale | 1753 |
| anhydrite | 1790 |
| shale, shells | 2000 |
| lime, shale | 2290 |
| lime, shale | 3815 |
| Arb. lime | 3824 |
| Total Depth | |

| | |
|------------------|------|
| Tops: | |
| Anhydrite | 1753 |
| Topeka | 3371 |
| Heebner | 3476 |
| Toronto | 3501 |
| Lansing | 3518 |
| Base Kansas City | 3741 |
| Conglomerate | 3784 |
| Arbuckle | 3813 |

DST #1 3814-24, open 1 hr., strong blow throughout test. Rec. 40' gas, 740' free oil, 80' muddy oil, BHP 500#.