

## WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

15-065-71955

Company- D. G. HANSEN

Farm- Bass "A"

No. 1

SEC. 13 T. 10 R. 21W  
SE SE NW

Total Depth. 3830 RB

Comm. 11-30-52

Comp. 12-11-52


Shot or Treated.

Contractor. C-G Drilling Co.

Issued. 8-8-53

County Graham

KANSAS



## CASING:

8 5/8 165.03'  
5 1/2 3846.46'

Elevation. 2273 RB

Production. Pot. 40 BO

Figures indicate Bottom of Formations.

|               |      |
|---------------|------|
| No listing to | 165  |
| shale & sand  | 1040 |
| shale         | 1230 |
| sand          | 1430 |
| red bed       | 1735 |
| anhydrite     | 1778 |
| shale         | 1800 |
| lime & shale  | 3550 |
| lime          | 3730 |
| lime & shale  | 3830 |
| Total Depth   |      |

## TOPS:

|                   |      |
|-------------------|------|
| Topeka            | 3293 |
| Heebner           | 3500 |
| Toronto           | 3519 |
| Lansing           | 3541 |
| Base KC           | 3766 |
| Weathered Simpson | 3817 |
| Arbuckle          | 3824 |

\*DST: 3633-45

CO to TD. Tstd 3 BFPH, 50% oil. Az.  
w/ 500 gals. Swbd. 1.7 BOPH. Az. w/  
1500 gals. Swbd. 4.5 BOPH. Took  
Pot. 6-4-53

## R B Measurements.

\*DST 3633-3645, rec. 2385' of muddy salt  
wtr in 30 mins. w/BHP 1390#, IFP 640#,  
1120# FFP