

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-02370


Company. D. G. HANSEN
Farm. Bass "A" No. 5

SEC. 13 T. 10 R. 21W
NE NW NW

Total Depth. 3883
Comm. 5-16-55 Comp. 5-25-55
Shot or Treated.
Contractor. C-G Drilling Co.
Issued. 7-9-55

County Graham

KANSAS



CASING:
8 5/8 168.73'

Elevation. 2278 DF

Production. Dry

Figures indicate Bottom of Formations.

shale & sand	168
shale	800
sand	890
sand & shale	1180
sandy shale	1240
sand	1495
red bed	1758
anhydrite	1798
shale & shells	2260
lime & shale	3828
cherty lime & shale	3852
lime & shale	3883
Total Depth	

TOPS:	
Anhydrite	1758
Topeka	3286
Heebner	3488
Toronto	3511
Lansing	3530
Base KC	3753
Conglomerate	3816
Arbuckle	3850

RB Measurements

DST. 3850-56, open 1 hr., very weak blow
increasing to weak blow for 55 min. &
then decreasing the other 5 min. Rec.
15' oil & 25' mud, BHP 25# Oil fairly
well spotted in mud.