

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas


15-065-01750

Company - SKELLY OIL CO.
Farm - C.R. Acheson No. 1

SEC. 14 T. 10 R. 21W
SW SW SE

Total Depth. 3749
Comm. 4-29-49 Comp. 5-20-49
Shot or Treated. Acid
Contractor. Claude Wentworth Drlg. Co. Inc.
Issued. 9-10-49

County. Graham
KANSAS



Elevation. 2181 Ind

Production. 514 bbls.

CASING:
3 5/8" 297' cem. w/150 sx.
5 1/2" 3741' cem. w/250 sx.

Figures Indicate Bottom of Formations.

surface clay & shells	60
shale & shells	302
Drilled 12 1/4" hole	
shale	450
shale & shells	555
shale, shells & sand	600
shale, sand & red bed	800
sand	920
shale & sand	1600
shale	1775
shale & shells	1965
shale	2250
shale & lime	2425
shale	2530
shale & lime	2940
shale	3020
lime & shale	3085
lime	3240
lime & shale	3300
lime	3740
dolo. brn cherty	3743
dolo. fine xyn.	3745
dolo. gry & brn xyn.	3747
dolo. gry brn xyn.	3749
Total Depth	

Tops:
Huebner shale 3394
Toronto lime 3415
Lansing lime 3436
Arbuckle 3740

3475-3495 good stain, spotted por.
3740-3745 fair por. & saturation
3745-3749 good " " " "

500 gals acid between 3741' & 3749'

I. P. before acid 1 gal. oil per hr.
I. P. after acid POB 8 hrs. 191.39 BO
to estab. 24 hr. SCC pot. of 514 bbls.

Producing formation:
Arbuckle lime 3741-3749