

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

15-065-01754


Company. ANDERSON-PRICHARD OIL CORP.
Farm. Lewis No. 1

SEC. 14 T. 10 R. 21W
SE SW

Total Depth. 3780'
Comm. 2-7-49 Comp. 2-21-49
Shot or Treated. Acidized
Contractor. Birmingham-Bartlett Drlg. Co.
Issued. 5-7-49

County. Graham

KANSAS



CASING:
8-5/8" 277' Cem. 1/175 Sx.
5-1/2" 3781' Cem. W/150 Sx.

Elevation. 2213 Ind.

2211 act

Production. 42 BOPH, no wtr.

Figures Indicate Bottom of Formations.

sand & shale	100
shale	460
shale & shells	1200
sand	1405
shale & red bed	1670
anhydrite	1710
shale & shells	2180
lime & shale	3457
lime K. C.	3494
lime	3590
lime & shale	3740
lime	3760
lime Arbuckle RTD	3776
lime ?	3780
Total Depth	

Tops, Corrected:

Heebner	3425
Lansing	3466
Arbuckle	3770

DST (Corr.) 3503-3525 open 30",
rec. 40' drlg. fluid, no oil,
no gas.

DST (Corr.) 3550-57, open 30",
gd blow, rec. 2760' salt wtr.,
no oil or gas.

Deepened to 3780', Swbd. 1 BOPH
Acid. 1/500 gals. after swbd.
load, swabd. 210 BO/5 hrs.
(42 BOPH) no wtr.