

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


15-065-00092

Company - ATLANTIC REFG. CO.
Farm - Miller No. 1

SEC. 15 T. 10 R. 21W
SE SE SE

Total Depth. 3844'
Comm. 3-19-49 Comp. 4-4-49
Shot or Treated.
Contractor. Armer Drlg. Co.
Issued. 4-30-49

County. Graham
KANSAS



CASING:
8-5/8" 285' Cem. W/275 Sx.

Elevation. 2189 feet

Production. 2187 act.
Dry

Figures Indicate Bottom of Formations.

post rock & shale	170
shale	240
shale & shells	775
sand	850
shale & sand	890
shale	1005
shale & sand	1075
shale & shells	1165
sand	1350
sand & shale	1430
shale & shells	1660
lime	1715
shale & shells	1735
shale, lime, shells	1920
shale & lime	2260
lime	2285
lime & shale	2735
lime	2790
lime & shale	2865
lime	2915
lime & shale	2975
lime	2990
lime & shale	3310
lime	3724
lime & shale	3804
lime	3844
Total Depth	

Tops:
Lansing 3467
Arbuckle 3819

Dry hole. Plugged 4-4-49

Heavy mud 3844 to 250' bridge
15 sx. cem. 250' to 190'
Heavy mud 190' to 45' 15 sx.
cem 45' to top.