


KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 065 — 21,244
County NumberS. 20 T. 10 R. 21 ²W

Loc. NW NW SW

County Graham

640 Acres
N

Locate well correctly

Elev.: Gr. 2284

DF KB 2293

Operator

Rains & Williamson Oil Co., Inc.

Address

435 Page Court Wichita, Kansas 67202

Well No.

#1

Lease Name

Noah

Footage Location

feet from (N) (S) line

feet from (E) (W) line

Principal Contractor

Rains & Williamson Oil Co., Inc.

Geologist

Paul Laird

Spud Date

6-19-80

Total Depth

3940'

P.B.T.D.

Date Completed

6-29-80

Oil Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
	12 1/4"	8 5/8"	20#	240'	50/50 poz.	225 sx.	2% gel, 3% cc.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water
	bbls. MCF
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1980
CONSERVATION DIVISION
Wichita, Kansas
CFPB

Operator Rains & Williamson Oil Co., Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole

Well No. #1 Lease Name Noah

S 20 T 10S R 21 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 - 3639-3660, 30 (30) 60 (30). Rec. 496' MSW. FP's 54-141, 163-262. IBHP 879, FBHP 868. Temp. 102°.			E. LOG TOPS	
			Heebner	3525 (-1232)
			Lansing	3562 (-1269)
			BKC	3800 (-1507)
			Conglomerate	3852 (-1559)
			Arbuckle	3916 (-1623)
			LTD	3926 (-1633)
DST #2 - 3894-3926, 30 (30) 30 (30). Rec. 5' mud. FP's 43-43, 43-54. IBHP 54, FBHP 43. Temp. 116°.				
DST #3 - 3555-3577, 30 (30) 30 (30). Rec. 15' mud. FP's 27-27, 36-36. IBHP 907, FBHP 799. Temp. 114°.				
DST #4 - 3685-3736, 30 (30) 60 (30). Rec. 475' WM. FP's 54-171, 171-270. IBHP 907, FBHP 471. Temp. 117°.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received
Wilson Rains
Signature
President
Title
7-22-80
Date

74942