

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-063-01762

Company - ANDERSON-PRICHARD OIL CORP.
Farm - Pierce No. 2

SEC. 23 T. 10 R. 21W
C N/2 S/2 NE

Total Depth. 3740
Comm. 6-1-51 Comp. 6-11-51
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 7-28-51

County. Graham
KANSAS



CASING:

8 5/8" 279 cem.
5 1/2" 3737 cem.

Elevation. 2172
2170(m)
Production. Phy. 221 bbls.

Figures Indicate Bottom of Formations.

surface clay	80
sand	125
shale	279
shale, shells	805
sand, shale	920
shale, shells, anhydrite	1050
sand, shale	1150
sand	1320
shale, sand	1410
shale	1500
sand, shale	1525
shale	1630
anhydrite	1675
red bed	1690
shale, shells	2130
shale	2220
broken lime, shale	2290
lime, shale	2930
shale	3025
lime, shale	3280
lime	3740 RTD
Total depth	

Tops:
Huebner 3393
Lansing 3433
Arbuckle 3732

DP & CO to bottom. Swb. 1 1/2
BOPH/10 hrs. No. wtr. AZ w/
500 gals. Max. Pressure 400#
Min. Press. 200#. Swb. 8 BOPH/
12 hrs and no wtr. Ran tubing
& rods. Pumped 80 BO in 12
hrs.