

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, **Wichita, Kansas**

15-065-00387

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Acheson **No. 1**

SEC. 24 **T.** 10 **R.** 21W
 SE SE SW

Total Depth. 3825'

Comm. 3-2-54

Comp. 3-12-54


Shot or Treated.

Contractor. Glenn W. Peel

Issued. 5-1-54

County Graham

KANSAS



Elevation. 3181' RB

Production. 91 Bbls. & NW

CASING:

8 5/8" 226' cem.

5 1/2" 3769' cem.

Figures indicate Bottom of Formations.

surface clay	80
sand	120
shale & sand	228
shale	250
shale & shells	1150
sand & shale streaks	1350
shale	1530
red bed & shells	1640
anhydrite	1680
shale & shells	2100
shale & lime	2430
lime	2560
lime & shale	2825
lime	2930
lime & shale	3165
lime	3758
Conglomerate	3767
Arbuckle	3770 RTD
Arbuckle	3775 1/2
Arbuckle	3789
Arbuckle	3825
Total Depth	

1 1/2 wtr. 8 hr. state test: 91 BOPD,
 no water.

Tops:

Heebner	3399
Toronto	3424
Lansing	3441
Base Kansas City	3668
Conglomerate	3719
Arbuckle	3767

DRILL STEM TESTS:

#1 3433-64; open 30 min., SI 15 min., weak blow 3 min., recov. 15' drilling mud, no show, BHP 1090#.

#2 3561-3630; open 60 min., SI 20 min., weak blow, recov. 180' HOCM, BHP 1090#.

Set 5 1/2" @ 3769' w/125 sx. MI & RUCT. Swbd. and bailed mud. Drilled shoe. C.O. to RTD 3770', no shows. Deepened to 3770-3775 1/2'. Acid. 250 gals. mx. press. 1400#, min., press. 700#. Swbd. off load 98 bbls., no shows. Deepened 3775 1/2 to 3789. Tested 3-4 gas. muddy wtr. per hr. Deepened 3789 to 3825. Tested 1 BWPH for 2 hrs. TD 3825. 4 hr. swab test 1 BWPH. Set Baker Cast Iron Plug @ 3718'. Perf. 3619-3625 w/6 shaped charges per ft. 4 hr. bailer test 1/2 GOPH. Acid 500 gal. swbd. off load wtr. and acid (102 bbls.) 6 hr. swab test 50 BO w/tr. wtr., last 3 hrs. @ rate of 6 BWPH w/tr. wtr. 10 hr. swab test 56 BO and no water. Set Halliburton plug @ 3190'. Perf @ 1650 w/2 7/16" holes, cem. thru porfs. w/300 sx 25 sx. stratcrete & 150 sx. SOW cem. Plugged back to 1575'. Drld. plug to T.D. 3710. POP. 24 hr. P test 94 BO and .6 of