

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-01763

Company. ANDERSON-RICHARD OIL CORP.
Farm. Acheson No. 2

SEC. 24 T. 10 R. 21W
NE SE SW

Total Depth. 3754'

Comm. 4-8-54


Comp. 4-19-54

Shot or Treated.

Contractor. Glenn W. Pool

Issued. 6-12-54

County Graham
KANSAS



Elevation. 2126' R.R.

Production. 265 Bbls/no wtr

CASING:

8 5/8" 255' com
5 1/2" 3750' w/600 sx com.

Figures Indicate Bottom of Formations.

surface clay-sand	120
shale	700
shale-sand	1140
sand	1390
shale	1655
Anhydrite	1695
shale-lime	2180
lime	2895
lime-shale	3043
lime	3160
lime-shale	3330
lime	3754
Total Depth	

TOPS:

Hoobner	3408
Toronto	3433
Lansing	3449
Baso Kansas City	3678
Conglomerate	3722
Arbuckle	3749

DST 1 1/2": 3750-54; op. 1 hr.,
recov. 55' oil & 50' HOCN,
BHP 765 1/2.

Drilled com & shoe. CO to
RTD 3754'. 5 hr. swab test
34 BO, no wtr. Ran tubing
& rods. POP. 23 hr. P test -
212 BO & no wtr.