

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-065-01765

Company- ANDERSON-PRICHARD OIL CORPORATION  
Farm- Acheson No. 4

SEC. 24 T. 10 R. 21W  
NE NE SW

Total Depth. 3758'  
Comm. 5-29-54 Comp. 6-7-54  
Shot or Treated.  
Contractor. Glenn W. Peel  
Issued. 7-24-54

County Graham KANSAS



Elevation. 2202' RB.

Production. 207 BO & no wtr.

CASING:

8 5/8" 224' cem.  
5 1/2" 3756' cem.

Figures indicate Bottom of Formations.

surface clay	40
sand and shale	160
shale	375
shale and sand	1225
sand	1400
red bed and shells	1555
red bed and shale	1645
anhydrite	1685
shale	1955
lime and shale	2320
lime	3100
lime and shale	3200
lime	3758 RTD
Total Depth	

Tops:

Anhydrite	1645
Topeka	3211
Heebner	3414
Toronto	3439
Lansing	3455
Base Kansas City	3677
Conglomerate	3727
Weath. Simpson	3741
Arbuckle	3754

DRILL STEM TESTS:

#1 3607-39, open 60 min., SI 20 min.,  
recov. 1740' gas, 900' muddy gassy oil,  
BHP 1090#.