

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-01774

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Herrold No. 3

SEC. 25 T. 10 R. 21W
NE SW NW

Total Depth. 3715

Comm. 3-5-53

Comp. 3-16-53


County Graham

KANSAS

Shot or Treated.

Contractor. Glenn W. Peel

Issued. 5-2-53



CASING:

8 5/8" 202' cem.

5 1/2" 3710' cem. w/125 sx

Elevation. 2132 RB
2129 (m)

Production. 66 BO / 0.2% wtr

Figures Indicate Bottom of Formations.

surface clay	202
shale	1620
anhydrite	1650
shale	2200
shale & lime	2485
lime	3080
lime & shale	3160
lime	3275
shale & lime	3330
lime	3713 RTD
lime	3715

Total Depth

Tops:

Anhydrite	1620
Topeka	3156
Heebner	3360
Toronto	3385
Lansing	3403
Simpson	3703
Arbuckle	3709

MICT and CO to RTD 3713'.

Swab 1 1/2 BOPH/4 hrs.

DD to 3715'. Swab 1 1/2

BOPH/7 hrs. Az w/250 gal.

max. pres. 800#, min. press.

450#. Swab 3 BOPH/10 hrs.

RT & R. Pumped 63 BO, no wtr.

in 17 hrs. 10-3/4" SPM. Pumped

72 BO, 2% water in 24 hrs.

10-3/4" SPM. Final report:

pumped 66 BO, 0.2% water in

24 hrs. 10-3/4" SPM.