

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-0605-01776


Company-ANDERSON-PRICHARD OIL CORPORATION
Farm-Herrold No. 5

SEC. 25 T. 10 R. 21W
NW NW NW

Total Depth. 3748 Corr.
Comm. 6-3-53 Comp. 6-12-53
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 8-1-53

County Graham

KANSAS



Elevation. 2147 RB

Production. 27 BOPD 1/4 BWPD

CASING:

8 5/8 205' cemented
5 1/2 3742' cemented

Figures indicate Bottom of Formations.

surface clay & sand	205
shale	1100
sand	1375
red bed	1615
anhydrite	1700
shale	1985
shale & shells	2020
salt	2050
lime & shale	2300
lime	2570
lime & shale	2910
lime	3050
lime & shale	3185
lime	3748
Total Depth	RTD corr

TOPS:

Topeka	3180
Heebner	3383
Toronto	3410
Lansing	3426
Conglomerate	3718
Simpson	3736
Arbuckle	3740

DST #1: 3711-48, open 1 hr. rec. 120'
HOCM, BHP 825#

Swbd & bld mud, drld shoe & CO to btm.
Dumped 1 B mud acid, CO & swbd .65 BOPH
12 hrs. Az 250 gal max press 350# no press
break. rec. 94 bbls load oil & acid.
12 hr swb test 1 1/2 BOPH tr watre.
POP. 14 hr P test, 28 BO, no water.
10 hr. P test 14 BO, no water. Re-az.
w/ 500 gal. pump in load oil. 14 hr.
P test 55 bbls load oil. Rec. remainder
load oil (22 BO & 14 B new oil) in 24
hts. P 16 BO, 2% water in 24 hrs.
P 11 BO, 1.2% water in 24 hrs. P 4 BO,
1.2% water in 6 hrs.