

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-01777

Company- ANDERSON*PRICHARD OIL CORP.
Farm- Herrold No. 6

SEC. 25 T. 10 R. 21W
NE NE NW

Total Depth. 3736'

Comm. 2-5-54


Shot or Treated.

Contractor- Glenn W. Peel

Issued. 4-10-54

Comp. 2-15-54

County Graham KANSAS



CASING:

8 5/8" 221' cem.
5 1/2" 3733' cem.

Elevation. 2169' R.B.

Production. 397 & no wtr

Figures indicate Bottom of Formations.

surface clay	40
shale	221
anhydrite	995
shale & shells	1025
shale	1625
anhydrite	1660
shale & shells	1900
shale & lime	2445
lime	2550
lime & shale	3295
lime	3736
Total Depth	3736

Tops:	
Heebner	3387 (-1218)
Toronto	3414 (-1245)
Lansing	3428 (-1259)
Conglomerate	3709 (-1540)
Simpson	3720 (-1551)
Arbuckle	3730 (-1561)
Total Depth	3736 (-1567)

DST #1: 3581-3621; op. 1 hr., recov.
15' oil and gas cut mud, BHP
200#.

DST #2: 3733-3736; op. 1 hr., recov. 910'
oil, BHP 700#.

Set 5 1/2" @ 3733'. MI & RUCT. Drilled show,
fillup 450' oil in 30 min. Swbd. 14 BOPH
FOR 6 HRS. POP. 14 hr. P test: 87 BO and

3 BW. 24 hr. Ptest: 154 BO and 3 BW. 24 hr. P
test: 149 BO and 3 BW. 24 hr. P
test: 142 BO and 3 BW. 24 hr. P test: 150
BO and 2 BW. 8 hr. state test: 397 BOPD
and no wtr.