

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-01778

Company- ANDERSON*PRICHARD OIL CORP.
Farm- Herrold No. 7

SEC. 25 T.10
SW NE NW

R21 W

Total Depth. 3752

Comm. 3-14-54


Comp. 3-24-54

County Graham
KANSAS

Shot or Treated.

Contractor. Glenn W, Peel

Issued. 5-8-54



CASING:

8 5/8" 243' cem

5 1/2" 3748' cem.

Elevation. 2186' R.R.

Production. 265 Bbls. oil & no
water

Figures indicate Bottom of Formations.

surface soils & sand	100
shale	1170
sand	1370
shale	1643
anhydrite	1680
shale	1815
shale & shells	2230
shale & lime	2435
lime	2550
lime & shale	2735
lime	3085
shale & lime	3200
lime	3670
lime & conglomerate	3720
conglomerate &	
Arbuckle	3752
Total Depth	

TOPS:

Anhydrite	1644
Topeka	3200
Heebner	3402
Toronto	3424
Lansing	3442
Base Kansas City	3673
Conglomerate	3720
Simpson	3735
Arbuckle	3747

DST #1: 3474-93; op. 60 min.,
SI 15 min., weak blow, recovered
305' oil & gas cut muddy
SW, BHP 1160#.

DST # 2: 3599-3628: op. 60
min., strong blow, recovered
300' gas, 120' HO&GCM and
450' muddy gassy oil, BHP 1130#

DST # 3: 3748-52: Op. 60 min.,
SI 20 min., strong blow,
recovered 570' free oil, 60'
muddy oil, BHP 790#.

Set 5 1/2" @ 3748'. Drilled plug
& CO to RTD. Swbd. 55 1/2 BO &
no water in 5 hrs. POP. 17 hr.
P test 128 BO, no water. 8 hr.
P test 57 BO, no water. 8 hr.
state test: 265 BOPD, no water.