


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-01779

Company- ANDERSON*PRICHARD OIL CORP.
Farm- Herrold No. 8

SEC. 25 T. 10 R. 21W
NE SE NW

County Graham KANSAS



Total Depth. 3725'

Comm. 3-26-54

Comp. 4-6-54

Shot or Treated.

Contractor. Glenn W. Peel

Issued. 5-8-54

CASING:

8 5/8" 251' cem.
5 1/2" 3720' cem.

Elevation. 2159 R.R.

Production. 217 Bbls oil & no
Water

Figures indicate Bottom of Formations.

surface clay & sand	100
shale	254
shale & shells	1110
sand	1620
anhydrite	1660
shale & shells	2090
lime & shale	2170
lime	2500
shale & lime	3115
shale & shells	3175
lime	3690
conglomerate	3720
Arbuckle	3725
Total Depth	

TOPS:

Topeka	3175
Heebner	3376
Toronto	3402
Lansing	3418
Base Kansas City	3646
Conglomerate	3694
Simpson	3704
Arbuckle	3719

DST # 1: 3575-3600; op 90
min., SI 20 min., weak blow
throughout, recovered 30'
O&GCM, 60' VHO&GCM w/some
free oil on bottom, BHP 300#
increasing.

DST # 2: 3720-25: op. 30
min., SI 20 min., recovered
530' oil, 30' HOCM, BHP 750#.

Set 5 1/2" @ 3720'. Drilled shoe
and CO to RTD 3725'. 8 hr. swab
test 106 BO and no water. POP.
8 hr. state test: 217 B OPD,
no water.