

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-01783

Company- HERMAN GEO. KAISER
Farm- White No. 2

SEC. 25 T. 10 R.21W
C E/2 SE SW

Total Depth. 3698'
Comm. 9-1-61 Comp. 9-12-61
Shot or Treated.
Contractor. H-30, Inc.
Issued. 1-13-62

County Graham
KANSAS



Elevation. 2112' DF

Production. 151 BOPD

CASING:

8 5/8" 208' cem w/150 sx.
5 1/2" 3689' cem w/125 sx.
DV Tool @ 1602' cem w/300 sx.

Figures Indicate Bottom of Formations.

surface clay	30	
shale & shells	159	
shale	208	
shale & shells	745	
sand	820	
shale & shells	1100	
sand	1280	
red bed & shale	1473	
red bed	1572	
Anhydrite	1610	
shale	1760	
shale & shells	2020	
shale	2180	
shale & lime	2210	
lime & shale	3140	
shale & lime	3230	
lime & shale	3275	
lime w/shale streaks	3316	
lime & shale	3433	
KC lime	3475	
lime & shale	3510	
lime	3545	
KC lime	3597	
lime & shale	3631	
lime	3671	
lime & shale	3698	RTD
Total Depth		

TOPS: SAMPLE

Anhydrite	1572
Base Anhydrite	1610
Heebner	3343
Toronto	3366
Lansing	3383
Kansas City	3607
Conglomerate	3661
Arbuckle	3688